



NOTE: 40" STANDING WORK BELOW TABLE TOP NOT POSSIBLE.

Equipment Layout



MINIMUM CEILING HEIGHT 8'-0"
RECOMMENDED CEILING HEIGHT 9'-0"

08239-A1

EQUIPMENT LEGEND

CFCI.....CONTRACTOR FURNISHED AND CONTRACTOR INSTALLED
OFCI.....OWNER FURNISHED AND OWNER OR CONTRACTOR INSTALLED
OFOI.....OWNER FURNISHED AND OWNER OR VENDOR INSTALLED

	ITEM	DESCRIPTION	SIZE	WT/LBS	BTU/HR	DETAIL SHEET
OFOI	①	QUANTUM ODYSSEY SERIES CONTROL CONSOLE WALL MOUNTED	18" W 12" D 5" H	12	130	
OFOI	②	QUANTUM ODYSSEY SERIES GENERATOR CABINET	24" W 20" D 35" H	380	4000	
OFOI	③	QUANTUM QS-510 FLOOR/WALL TUBESTAND	120" L 38" D 85" H	508	873	
OFOI	④	QUANTUM QW-420 VERTI-Q WALL STAND	27" W 13" D 84" H	225	N/A	
OFOI	⑤	QUANTUM QT-750 RADIOGRAPHIC TABLE	79" W 36" D 33" H	500	230	
OFOI	⑥	FUJI CARBON X CR SYSTEM	23" W 15" D 45" H	314	XXX	
OFOI	⑦	FUJI LITE IIP WORKSTATION CPU ON WALL MOUNT	5" W 14" D 16" H	60	1200	
OFOI	⑧	FUJI LITE IIP WORKSTATION FLAT PANEL MONITOR ON WALL MOUNT	17" W 10" D 19" H	26	300	
OFOI	⑨	FUJI LITE IIP WORKSTATION KEYBOARD ON WALL MOUNT	18" W 7" D 2" H	2	N/A	
CFCI	⑩	LEAD GLASS VIEW WINDOW	24" W 24" H	N/A	N/A	

CUSTOMER:

Equipment Layout / Legend

THESE DRAWINGS ARE SUBMITTED TO SUGGEST LOCATION OF ALL DIAGNOSTIC IMAGING EQUIPMENT AND ASSOCIATED APPARATUS, ELECTRICAL WIRING DETAILS, AND ROOM ARRANGEMENTS. IN PREPARING THIS DRAWING, EVERY EFFORT HAS BEEN MADE TO CONFORM DETAILS TO THE ACTUAL EQUIPMENT EXPECTED TO BE INSTALLED. HOWEVER, THESE DRAWINGS ARE NOT TO BE USED FOR ACTUAL CONSTRUCTION PURPOSES, AND THE PREPARER CANNOT ACCEPT ANY RESPONSIBILITY FOR DAMAGES RESULTING THEREFROM. CONSTRUCTION DRAWINGS TO BE PREPARED BY PURCHASER'S ARCHITECT OR CONTRACTOR.



DRAWN BY:
R. Rider
DATE:
07/15/08
DWG. NO.
08239
SHEET:
A1